



## Westfield Insurance Studio Theatre Technical Specifications

**Stage Door:** 1410 Dodge Ct, Cleveland, OH 44114 - **24 Hr. Receiving Address (Central Security):** 1650 Chester Ave, Cleveland OH 44114

### Stage Specifications:

#### Seating Capacity:

- Option A: (217) + (75) in Balcony (292)
- Option B: (183) + (75) in Balcony (258)
- Option C: (132) + (75) in Balcony (207)
- Option D: (166) + (75) in Balcony (241)

**Playing area:** (28'-0" w X 30'-0" d)

#### Stage Deck to:

- Catwalk: (25'-0")
- Balcony Rail: (20'-2")

#### Plaster Line to:

- Last Line Set #: (29'-9")
- Up Stage Wall: (32'-5")

**Number of Battens:** (3) Automated fly system

**Length of Battens:** (36'-0")

**Distance between Battens:** (1'-01")

**Travel of Battens:** (28'-0")

**Last Lineset (#3) to Up Stage Wall:** (3'-0")

**Weight Capacity:** (1,000lbs)

**Loading Dock Door:** (7'-7" w X 10'-8" h)

**Elephant Door:** (7'6" w X 16' h)

**Freight Elevator:** (8'-9" w X 15'-8" l) - 40,000lbs capacity

### House Audio:

**House Audio Console:** Yamaha QL1

**Mixing Position:** (32'-10") from Plaster Line

**House Amplifiers:** (4) Nexo 4x1

#### House Speakers:

- (6) Nexo Geo M620
- (4) EAW 109
- (2) EAW 18" subwoofers

#### Microphone Inventory:

2	Shure Beta SM58	1	Shure QLXD SM57
---	-----------------	---	-----------------

### House Video:

**Projector:** Panasonic PT-SZ21K2 (20,000 Lumens)

**Video Control:** Blackmagic ATEM Switcher

**Projector Screen:** (13'-0" w X 10'-0" h)

**Project to Screen Distance:** (41'-0")

### House Lighting Equipment:

Theatre is contracted with House Plot unless noted, contact Director of Production for details.

#### Inventory:

- (47) - Strand SL 19° ellipsoidal
- (36) - Strand SL 26° ellipsoidal
- (38) - Strand SL 36° ellipsoidal
- (24) - ETC Source Four PAR, WFL
- (30) - Altman Fresnel 8" 175Q
- (20) - L&E Broad Cyc

**Lighting Control:** ETC Ion Console

**Dimmers:** 272 - 2.4kw

### House Soft Goods:

#### Legs:

- 12 @ (10'-0" w X 20'-9" h)
- 4 @ (10'-0" w X 25'-0" h)

**Borders:** - 4 @ (50'-0" w X 16'-0" h)

#### Drops:

- 1- Black Scrim @ (48'-0" w X 20'-10" h)
- 1- Blackout/2-panel @ (27'-0" w X 20'-09" h) ea.
- 1 Cyclorama @ (54'-0" w X 41'-8" h) - natural muslin

### PDF Drawings are available at:

<https://www.playhousesquare.org/about-playhousesquare-main/rent-our-spaces/stage-and-theatrical-specs>

### Playhouse Square Production Department Contact List:

**Director of Production:** Penny Zaletel (216) 640-8546  
([Penny.Zaletel@playhousesquare.org](mailto:Penny.Zaletel@playhousesquare.org))

**Sr. Production Manager:** Jody Dagg (216) 640-8548  
([Jody.Dagg@playhousesquare.org](mailto:Jody.Dagg@playhousesquare.org))

**Production Manager:** Tony Hanf (216) 640-8670  
([Tony.Hanf@playhousesquare.org](mailto:Tony.Hanf@playhousesquare.org))

**Technical Project Manager:** Liam Roth (216) 329-0344  
([Liam.Roth@playhousesquare.org](mailto:Liam.Roth@playhousesquare.org))

**Production Manager:** Heather Cochran (216) 373-135  
([Heather.Cochran@playhousesquare.org](mailto:Heather.Cochran@playhousesquare.org))

**Production Supervisor:** Daniel Zilka (216) 373-3711  
([Daniel.Zilka@playhousesquare.org](mailto:Daniel.Zilka@playhousesquare.org))



# Westfield Insurance Studio Theatre Technical Specifications

## Production Map

